

ASBESTOS REVIEW SUMMARY

SELECT MANSFIELD APARTMENT BUILDINGS

UPDATED: May, 2019

ND = NO ACM DETECTED

ITEM TESTED	BLDG 2	BLDG 3	BLDG 15	BLDG 16	BLDG 17
Ceiling Plaster	ND	ND	ND	ND	ND
Joint Compound	ND	ND	ND	ND	ND
Dark Grey Wall Block	ND	ND	ND	ND	ND
4" Black Cove Base	ND	ND	ND	ND	ND
Cove Base Adhesive	955 LF	1,375 LF	1,750 LF	1,170 LF	1,270 LF
9" Sq Kitchen Floor Tile	2,588 SF	3,539 SF	3,078 SF	796 SF	991 SF
9" Sq Tile Adhesive	2,588 SF	3,539 SF	3,078 SF	796 SF	991 SF
12" Sq Kitchen Floor Tile	ND	ND	ND	ND	ND
12" Sq Tile Adhesive	ND	ND	ND	ND	ND
Black Stair Treads	ND	ND	ND	ND	ND
24" Transite Piping	50 LF	75 LF	75 LF	50 LF	75 LF
Fiberglass Insulation	ND	ND	ND	ND	ND
White Sealant (for ACM)	ND	ND	ND	ND	ND
Potential PCB's	Not Tested	Not Tested	Not Tested	Not Tested	Not Tested